



ADDENDUM # 3

Whiting Lane Elementary School Main Entrance Security Renovation

BID # 200042

June 18, 2020

Dear Vendors:

The Contract Bidding Documents pursuant to Bid # 200042 are hereby revised as follows. Bidders shall acknowledge this addendum in their bid response:

CLARIFICATIONS:

Q1. Veneer species for wood doors are not specified, please advise.

A1. AWI Premium Grade, book matched, Plain Sliced Red Oak veneer faced panels

Q2. Please specify wood doors **finish type** (Primed, stained).

A2. Stained clear

Q3. Door #113 to have **electric strike** on the drawings, however, it shows with **electrified lockset** on the specs.

A3. Electronic mortise lever set; Corbin Russwin ML20906 X SEC – NSA 626; provide – power supply, BPS-24-4 (24VDC @ 4 amps), Provide necessary relays

Q4. Hardware sets 4 and 403 don't exist on the specs. Please advise.

A4. Hardware Set 004 for Door 110: 1 Hinge, Continuous Geared 780 - 112 HD - 83" - CLEAR - Concealed Leaf - Roton RETW-QC (12-Wire) 1 Mortar Box 430 Hager 1 Electrically Unlocked ML20906 x SEC - LC - NSA - 626 - M17 - M91 - M92 - Corbin-Russwin 24 Volt AC/DC 1 Door Harness Door Harness with "QC" Connectors to match Door McKinney Hardware 1 Cylinder, Mortise Cylinder - Mortise - 626 Section 087100 1 Closer, Overhead Parallel Arm CLP-7500 - 689 (Set Stop Arm at 90 Degrees) Norton 1 Power Supply BPS-24-1 (24VDC @ 1 Amps), (Provide Necessary Securitron Relays) 1 Door Contact Door Contact By Others 1 Diagrams - Elevation and Riser By MFR 1 Diagrams - Point To Point By MFR

Hardware Set 403 for Door 114: 3 each Hinge, Ball Bearing; 1279 – 4 ½"x4 ½" – US26D Hager; 1 each Lockset, Storeroom/Closet 737P 8204 LNL – SU26D Corbin Russwin; 1 each Closer, Overhead regular arm TB 351 PS (EN) LCN; 1 each Kick Plate K1050 – 8"x34" – 18 ga. US32D Rockwood; 1 each Stop, Wall 409-US26D Rockwood; 3 each Silencer, HM Dr. Frame 608-RKW-Gray Rockwood

Q5. Drawings hardware schedule is asking for **LCN 4000 series** Closers , however, specs hardware schedule is asking for **Norton 7500**.

A5. LCN 4111 CUSH



Q6. On the finish schedules were AP-1 is called out for the ceilings are these rooms to get all new tiles.

A6. AP-1 as defined in Addendum 2

Q7. We would like to know if all the new walls go to the deck and also if they are rated.

A7. All the new walls will all go to deck, ballistic doors and frames have to anchor to structure, sheet rock too and we intend to seal any penetrations. There are no rated walls only smoke barriers from the corridors.

Q8. PT-1 on Finish Drawing A5.0 calls for POLOMYX – Zolotone in Vestibule

Can Benjamin Moore Ultra Spec Scuff X be used in lieu of Polomyx?

A8. Yes

Q9. One of my millwork suppliers that we have used for over 20yrs has asked if Section 06402 1.5C would be required on these projects.

A9. Line Item C can be disregarded.

Thank you,

Rick Hyman

Buyer

Cc: Bill Phibbs, Capital Projects Manager

J. Kirk Bostwick, AIA Bostwick Architects LLC

END OF ADDENDUM # 3