



ADDENDUM # 1
HALL HIGH SCHOOL
ROOF REPLACEMENT AREA F
BID # 200044

June 30, 2020

Dear Vendors:

The Contract Bidding Documents pursuant to Bid # 200044 are hereby revised as follows. Bidders shall acknowledge this addendum in their bid response:

CHANGES TO DRAWINGS:

DRAWING H-1

GENERAL NOTES:

Add: Note 2. "REMOVE THE METAL PARAPET COPING ON THE SOUTH, EAST, & WEST SIDES OF ROOF F. THE JOINTS BETWEEN THE PIECES OF COPING HAVE ASBESTOS-CONTAINING ROOFING CEMENT. SNIP OFF THE COPING WITH ASBESTOS-CONTAINING ROOFING CEMENT AND DISPOSE OF THE SNIPPED-OFF PIECES AS ASBESTOS WASTE. THE TAR PAPER UNDER THE METAL PARAPET COPING IS NOT ASBESTOS-CONTAINING."

Add: Note 3. "REMOVE THE CONTROL JOINT SEALANT FROM THE 3 PARAPET WALL LOCATIONS NOTED ON DRAWING R-1 ALONG THE SOUTH WALL OF ROOF F. PLACE THE REMOVED SEALANT IN A 5 GALLON BUCKET AND TURN BUCKET OVER TO OWNER FOR DISPOSAL."

REVISED COMPLETION DATES:

The Substantial and Final Completion Dates have been revised as follows:

Substantial Completion Date – August 26, 2020

Final Completion Date – August 31, 2020



CLARIFICATION:

Q1. What building automation contractor is in the school currently?

A1. SNE Systems

Thank you,

Rick Hyman

Buyer

Cc: Bill Phibbs, Capital Projects Manager
W. Albert Jacunski, AIA

END OF ADDENDUM # 1